BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Improvements & Constructions of CC Road at Coconut Garden (Ismail Graden) to Mahalakshmi Nagar in Ward No.14.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Scarifying the surface and dressing KSRRB 300-44 Scarifying top bituminous surface or surface dressing or premix carpet including picking up scarified materials, stacking of old serviceable materials within a lead of 100 metres by manual means including cost of all abour charges complete as per specifications.	Sqm	980.20	17.93	Rupees Seventeen and Ninety Two Paise Only
2	Construction of Embankment with Material Gravel / Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel / Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications.(which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) complete as per specifications.	Cum	225.45	146.88	Rupees One Hundred Forty Six and Eighty Eight Paise Only
3	Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	245.05	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
4	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	147.03	3884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
5	Providing and laying in position plain cement concrete of design mix M20 with OPC cement @320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reafirmed-2008, machine mixed, concrete laid in layers not blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	122.53	4409.64	Rupees Four Thousand Four Hundred Nine and Sixty Four Paise Only

Signature of the Contractor

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer

6	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	42.88	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, c10ser blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	75.40	683.70	Rupees Six Hundred Eighty Three and Seventy Paise Only
8	Vaccum de-watering with vaccum pump and suction mat and compaction wath skin floater clubbed with floating disc including cost of generator, HOM of machinery, screned vibratory, power floater, blade and disc., with all lead and lift. complete as per specifications.	Sqm	942.50	84.80	Rupees Eighty Four and Eighty Paise Only
9	Providing and fixing in position 20 mm thick premoulded joint filler in expansion joint for fixed ends of simply supported spans not exceeding 10 m to cater for a horizontal movement upto 20 mm, covered with sealant complete as per drawing & Technical Specification complete as per specifications.	M	70.00	167.48	Rupees One Hundred Sixty Seven and Forty Eight Paise Only

Signature of the Contractor

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division,